POWERED BY PARKER 3000 HP POSTED BARGE RIG

DRILLING DEPTH RATING:

Drilling 25,000' w/5" drill pipe

LIGHTSHIP:

(Towing Draft) 7'8" (Towing Height) 75'

BARGE DIMENSIONS, SPECIFICATIONS:

214.5' Length 72' Beam Hull Depth 14' 14' Posted Deck Height Key Slot 20' x 45' 40' Main Deck to Rotary Pan Main Deck to Trolley Beams 38.8 Accommodations 86 bunks

+ Medical treatment room

CAPACITIES:

Potable water 892 barrels
Drill water 4,256 barrels
Fuel 1,902 barrels

Mud tank capacity:

Active 1,140 barrels
Reserve 1,235 barrels
Trip Tank 100 barrels



Bulk Storage: 3x740 cu/ft
2x745 cu/ft
Surge tank 1x70 cu/ft
Sack Storage 300 K

(1) Slugging pit 60 barrels

Equipped for full zero discharge operations for work within environmentally sensitive areas.

DRAWWORKS:

- Oilwell E-3000 (3000 HP) with 7838 Elmago brake system w/(3) ea. GE-752 traction motors (1000 hp input each)

MUD PUMPS:

- (2) A1700 PT (1700 hp) Triplex pumps w/2 each GE-752 traction motors (800 hp input each)

MAST AND TRAVELING EQUIPMENT:

- Mast: 172' L.C. Moore Jack knife; 1,300,000 lb static hookload capacity on 14 lines
- Block: Oilwell 650 ton; (7) 60" sheaves for 1 1/2" drill line
- Crown: L.C. Moore 650 ton
- Substructure: 1,000,000 lbs. w/ 500,000 lbs setback capacity
- Rotary Table: Oilwell 37 1/2"
- Top Drive: CanRig; 650 ton capacity; Hi torque w/(1) ea GE-752 traction motor (900 hp input)

WELL CONTROL EQUIPMENT:

- 13 5/8" 5,000 psi Hydril GK annular preventer; 13 5/8" 10,000 psi Cameron double ram, Type U; 13 5/8" 10,000 psi Cameron single ram, Type U; 10,000 psi manifold

Note: Other BOP equipment available from stock



Note: equipment subject to client-specific requirements

MUD HANDLING/SOLIDS CONTROL:

Shale Shaker
 Mud Cleaner
 Desander
 Desilter
 Degasser
 Mud Agitators
 (4) Derrick Flo-Line Cleaners
 Derrick High G Dryer
 Derrick 10" x 2 cones
 Derrick 4" x 20 cones
 SWACO
 (16)

POWER & ELECTRICAL SYSTEM:

- (1) Ross Hill SCR system. Model 1400
- (3) Diesel generator set EMDs Model MD 12645E8 w/ AB-20-6 brushless generators producing 600 V, AC each
- Caterpillar D-379 emergency generator w/SR-CR 480 VAC, 500 KW generator

TUBULARS:

- 5" drill pipe w/handling tools, 15 joints of 5" heviwate, drill collars (8", 7 1/4", or 6 1/2" as available from Contractor's stock)

MISCELLANEOUS EQUIPMENT:

- Unit Mariner 50' boom SWL 20 ton crane
- Sea King 60' boom, SWL 25 ton crane

