

Year Modified: 2020

Rated Drilling Depth

5 in. Drill Pipe: 18,000 ft (5,486 m)
4-1/2 in. Drill Pipe: 23,000 ft (7,010 m)

Mast

Make: Pyramid
Height: 142 ft (43.3 m)
Max. Hookload: 1 million lbs
Racking Capacity: 5 in. drill pipe – 18,000 ft. (5,486 m)

Drawworks

Make: Gardner Denver 1500E
Rated Input: 2,000 hp (1,491 kW)
Input Power: Two (2) GE-752 DC traction motors, each rated 1,000 hp (746 kW)
Drilling Line: 1-3/8 in. (34.9 mm)

Traveling Equipment

Traveling Block: Oilwell
Max. Load: 1 million lbs
Swivel: Continental Emsco LB-500
Max. Load: 1 million lbs

Substructure


Make, Type: Pyramid, swing-up
Clear Working Height: 21 ft (6.4 m)
Setback Load: 600,000 lbs

Rotary Equipment

Top Drive: Tesco TD-500HS
Input Power: Detroit 16V-92, 1,100 hp (820 kW)
Rotary Table: Oilwell 37-1/2 in. (952.5 mm)
Input Power: Driven by drawworks
Static Load Rating: 1.2 million lbs

BOP System

Annular Preventer: One (1) 13-5/8" Hydril 5,000 psi
Ram Preventers: One (1) 13-5/8" Cameron 10,000 psi single ram
One (1) 13-5/8" Cameron 10,000 psi double ram



Gensets

Engines: Three (3) Caterpillar 3512B diesel engines; 1,476 hp (1,101 kW) @ 1,200 rpm each
Generators: Three (3) Caterpillar SR4B generators, 1,050 kW (1,313 kVA) each

Power Distribution

Gen. Control: Three (3) Ross Hill Model 1400
SCR: Three (3) Ross Hill Model 1400 bays
MCC: 600/480/208/120 volts

Mud Pumps

Pumps: Three (3) Continental Emsco FB-1600 triplex pumps; each rated 1600 hp
Input Power: Each pump driven by two (2) GE 752, one (1) GE EMD-D79 DC traction motors, each rated 800 hp

Mud Handling/Solids Control

Active Mud System: 1,590 bbls (253 m³)
Shale Shakers: Three (3) Derrick FLC-514 4-panel; 1680 gpm total
One (1) Derrick High-"G" dryer FLC-2000
Degasser: Swaco vacuum-type; 1,000 gpm



Note: Equipment subject to client-specific requirements. No part of this document may be reproduced or transmitted without prior consent of Parker Drilling. Rev 12/19

Energy. Well engineered.


Find out more at parkerwellbore.com

©2021 Parker Wellbore. All Rights Reserved.



2103 CityWest Blvd Suites. 300-400
Houston, TX 77042

Rig Plot Plan



Note: Equipment subject to client-specific requirements. No part of this document may be reproduced or transmitted without prior consent of Parker Drilling. Rev 12/19